

WORKED EXAMPLE

Jack Mo reads it aloud

Curtain-wall glazing

THE UNTRAINED EYE vs THE RISK MANAGER'S EYE



Jack Mo circles what his eye lands on — and the one thing that should be there and isn't.

To a passing eye this is the good part — the building is getting its face. Big panels of glass and aluminum rise up the frame, catching the light, and the tower finally looks finished from the street. A risk manager looks at the same skin and feels the schedule tighten behind it. They don't see glass; they see the one thing that closes the building, and every trade waiting inside for it. These units are custom, fabricated to order, which means long lead. They can't be bought down the street. So the trained eye stops on a single panel and asks the next question: what happens to everyone inside if this one arrives late, or arrives cracked? The answer is that dry-in slips. Until the skin is closed the interior is not dry, and no finish trade can start, so one late panel holds up drywall, paint, flooring, ceilings — the whole inside of the building. Open floors keep taking weather until that skin is sealed, inviting damage and rework on work already done. And each panel is a heavy lift at height, swinging over a live street. The ordinary eye sees a building looking finished and relaxes. The trained eye sees a building still open and traces the chain of dependents hanging off it. The scene did not change between those two readings. The eye did.

THIS SCENE FEEDS YOUR REGISTER

R3 • R7 • R11 • R45 • R49 — the five students dealt this scene.

The discipline under that read

The moves you run so you can see it too — then five register rows fall out of one glance.

- LOOK

sweep overhead → working level → ground/openings → edges → background (don't lock on the obvious).
- SPLIT

say what you SEE — facts only: Large glass-and-aluminum curtain-wall units going up the face of the building, Panels are custom-fabricated to order, which makes them long-lead items, Floors behind the skin are still open and exposed to weather.
- NOTICE

circle the cues: The open floors behind the unset panels; A panel mid-lift swinging over the street; The gap in the skin where the next unit goes — and the missing There is no second source for these panels. Because the curtain-wall units are custom-fabricated to order, nothing on this site or down the street can replace a panel that shows up late or damaged — the missing thing is any fallback, so the whole dry-in date rides on one supplier delivering whole and on time.
- ASK → PROJECT

what releases it, who's in the path, what happens next — and in which phase.

NAME · five rows, born from one glance (cause → event → consequence)

- 1

Schedule

Because the curtain-wall units are custom-fabricated to order and long-lead, a panel may arrive late, leading to dry-in slipping and the interior finish sequence pushing out.
Owner: Project Manager · Trigger: a glazing-delivery date on the procurement log moving past its need-by date
- 2

Schedule

Because no finish trade can start until the building is dried in, a single late or missing panel may hold the skin open, leading to drywall, paint, and flooring crews sitting idle inside.
- 3

Quality

Because the floors stay open to weather until the skin is closed, rain or wind may reach the interior, leading to damaged work and rework on finishes already in place.
- 4

Schedule

Because each unit is shipped and handled individually, a panel may arrive cracked or be damaged on site, leading to a replacement reorder on the long-lead clock and a further dry-in delay.
- 5

Safety

Because heavy panels are lifted and set at height over a live street, a dropped or struck load may occur, leading to a serious injury to workers or the public below.

READING MOVE · bank this card
“When you see a building's skin going on, trace what depends on it finishing — follow the chain of trades that can't start until the building is dried in, and that chain of dependents is where the schedule risk lives.”

SUCCESS CARD · check the read against these six

- ☐ a real, visible cue

☐ cause is a site condition

☐ a future event

☐ consequence on cost/time/quality/safety
- ☐ owner + early-warning trigger

☐ (M4) P and I each defended

P × I? Not yet — Module 2 IDENTIFIES; Module 4 ASSESSES. These rows seed register rows R3 · R7 · R11 · R45 · R49.